

SYMBOLS

	CENTERLINE
	PROPERTY LINE
	FENCE LINE
	RIGHT OF WAY
	POWER LINE
	SEWER LINE (INDICATE SIZE)
	STORM DRAIN (INDICATE SIZE)
	WATER LINE
	NATURAL GAS LINE
	FLOWLINE
	GUARDRAIL
	AC DIKE
	EXISTING EMBANKMENT SLOPE
	NEW EMBANKMENT SLOPE
	BO BLOW OFF
	FH FIRE HYDRANT
	RED REDUCER
	TB THRUST BLOCK
	WM WATER METER
	WCAP WATER PLUG
	WV WATER VALVE
	CULVERT
	DI DRAIN INLET
	CO CLEAN OUT
	MH MANHOLE
	UTILITY POLE
	STREET LIGHT
	SIGN
	TREE
	BARRICADE

YUBA COUNTY GENERAL NOTES

GENERAL:

- ALL CONSTRUCTION MATERIALS AND WORKMANSHIP SHALL CONFORM TO THE LATEST EDITION OF THE YUBA COUNTY IMPROVEMENT STANDARDS, THE CALIFORNIA DEPARTMENT OF TRANSPORTATION (CALTRANS) STANDARD SPECIFICATIONS, AND ANY OTHER APPLICABLE AGENCY STANDARDS.
- CONTRACTOR SHALL HAVE APPROVED PLANS IN HIS POSSESSION AND SHALL SCHEDULE PRECONSTRUCTION MEETING PRIOR TO CONSTRUCTION.
- TO SCHEDULE A PUBLIC WORKS INSPECTION, CALL (530) 749-5656 AT LEAST TWO (2) WORKING DAYS PRIOR TO INSPECTION, EXCLUDING WEEKENDS AND HOLIDAYS.
- IF WORK IS BEING DONE WITHIN THE COUNTY RIGHT OF WAY, CONTRACTOR SHALL OBTAIN AN ENCROACHMENT PERMIT FROM PUBLIC WORKS PRIOR TO COMMENCEMENT OF CONSTRUCTION.
- CONTRACTOR SHALL SUBMIT A SITE SPECIFIC TRAFFIC CONTROL PLAN TO PUBLIC WORKS FOR APPROVAL AT LEAST TWO (2) WORKING DAYS PRIOR TO THE PRECONSTRUCTION MEETING, EXCLUDING WEEKENDS AND HOLIDAYS. ANY CHANGES TO THE TRAFFIC CONTROL PLAN SHALL BE SUBMITTED TO PUBLIC WORKS FOR APPROVAL PRIOR TO CONSTRUCTION. FIELD MODIFICATIONS MAY BE REQUIRED AS DIRECTED BY THE PUBLIC WORKS DEPARTMENT.
- CONTRACTOR SHALL PROVIDE FOR PUBLIC SAFETY AND TRAFFIC CONTROL IN ACCORDANCE WITH STATE OF CALIFORNIA MANUAL OF TRAFFIC CONTROLS. CONTRACTOR SHALL PROVIDE FOR SAFE VEHICULAR AND PEDESTRIAN ACCESS AT ALL TIMES DURING CONSTRUCTION.
- CONTRACTOR SHALL CONTACT ALL UTILITY COMPANIES FOR VERIFICATION OF THE LOCATIONS OF ALL UNDERGROUND FACILITIES. CALL UNDERGROUND SERVICE ALERT (USA) AT 1-800-227-2600 TWO (2) WORKING DAYS BEFORE ANY EXCAVATION. THE CONTRACTOR SHALL CONTACT THE PUBLIC WORKS DEPARTMENT 8 WORKING DAYS PRIOR TO ANY WORK NEAR COUNTY OPERATED TRAFFIC SIGNALS FOR MARKING OUT FACILITIES. IF THE CONTRACTOR FAILS TO NOTIFY THE COUNTY AND DAMAGES TO TRAFFIC SIGNAL FACILITIES OCCUR, THE CONTRACTOR WILL BE RESPONSIBLE TO PAY ALL COSTS TO REPAIR THE DAMAGED FACILITIES.
- THE CONTRACTOR IS RESPONSIBLE FOR THE PRESERVATION OF PROPERTY AND PUBLIC SAFETY PER SECTION 7 AND 15 OF THE STATE'S STANDARD SPECIFICATION.
- CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING MONUMENTS AND OTHER SURVEY MARKERS. MONUMENTS AND SURVEY MARKERS DESTROYED DURING CONSTRUCTION SHALL BE REPLACED BY A LICENSED LAND SURVEYOR AT THE CONTRACTOR'S EXPENSE. CONTRACTOR SHALL PROVIDE COUNTY SURVEYOR WITH 2 WORKING DAYS NOTICE PRIOR TO MONUMENT REPLACEMENT.
- THE PRIME CONTRACTOR SHALL DESIGNATE A PERSON(S) WHO SHALL HAVE THE AUTHORITY TO REPRESENT AND ACT FOR THE CONTRACTOR ON THE JOB SITE DURING ALL WORKING AND NON-WORKING HOURS AND PROVIDE PUBLIC WORKS WITH CONTACT AND EMERGENCY CONTACT PHONE INFORMATION. THIS INCLUDES ALL WORK BEING PERFORMED INCLUDING SUBCONTRACTED WORK.
- CONTRACTOR SHALL HAVE APPROVED PLANS AVAILABLE ON SITE DURING CONSTRUCTION AND CONTRACTOR SHALL CONSTRUCT ALL IMPROVEMENTS TO THE LINE AND GRADE SHOWN ON THE PLANS. ANY DEVIATION FROM THE PLANS SHALL REQUIRE THE WRITTEN APPROVAL OF PUBLIC WORKS.
- THE CONTRACTOR SHALL BE IN COMPLIANCE WITH DUST CONTROL PER SECTION 10, STATE OF CALIFORNIA STANDARD SPECIFICATIONS AND AS REQUIRED BY THE FEATHER RIVER AIR QUALITY MANAGEMENT DISTRICT.
- WHERE WORK IS TO BE DONE IN AN OFF-SITE EASEMENT, THE CONTRACTOR SHALL NOTIFY THE PROPERTY OWNER IN WRITING AT LEAST 2 WORKING DAYS PRIOR TO COMMENCING WORK.
- CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF EXISTING TRAFFIC DELINEATION AND SIGNS. ANY TRAFFIC DELINEATION OR SIGNS DAMAGED DURING ROAD CONSTRUCTION SHALL BE REPLACED WITH LIKE KIND OR AS APPROVED BY PUBLIC WORKS AT THE CONTRACTORS EXPENSE.
- PRIOR TO PLACING CURB, GUTTER, SIDEWALK, ASPHALT CONCRETE, OR BASE MATERIAL, ALL UNDERGROUND FACILITIES WITHIN THE ROAD RIGHT-OF-WAY SHALL BE INSTALLED, BACKFILL COMPLETED, AND THE CONTRACTOR SHALL SUBMIT DOCUMENTATION TO THE YUBA COUNTY PUBLIC WORKS DEPARTMENT THAT EACH OF THE UTILITY COMPANIES HAVING FACILITIES WITHIN THE WORK AREA HAVE SATISFACTORILY PASSED ACCEPTANCE TESTS.

YUBA COUNTY
DEPARTMENT OF PUBLIC WORKS

GENERAL NOTES,
SYMBOLS & ABBREVIATIONS

APPROVED BY:  DATE: 8/12/26

001