



1. CURB, GUTTER AND SIDEWALK SHALL BE CONSTRUCTED OF 6 SACK CONCRETE IN ACCORDANCE WITH CALTRANS STANDARD SPECIFICATIONS.
2. ALL CURB GUTTER AND SIDEWALK SHALL HAVE A BROOM FINISH.
3. VERTICAL CURB AND GUTTER TO BE USED AT ALL CURB RETURNS WITH A 1/2" EXPANSION JOINT AT BOTH ENDS.
4. GUTTER PAN CROSS SLOPE NOT TO EXCEED 5% MAXIMUM, OR BE LESS THAN 4% MINIMUM.
5. AGGREGATE BASE AND SUBGRADE TO BE COMPACTED TO MINIMUM OF 95% RELATIVE COMPACTION.

YUBA COUNTY
DEPARTMENT OF PUBLIC WORKS

CURB AND GUTTER
DETAILS

APPROVED BY:

8/12/20
DATE:

YUBA COUNTY DEPARTMENT OF PUBLIC WORKS	
CURB AND GUTTER DETAILS	
APPROVED BY: 	DATE: 8/12/06
201	